

Dwarka Expressway Mixed-Use District

AI-generated development appraisal — Yield Max concept

Generated on 19 July 2026 · Gurugram, Haryana · Sanctioning authority: DTCP Haryana / GMDA

1 · Project brief

Project name	Dwarka Expressway Mixed-Use District
Development type	Mixed-Use
Jurisdiction	Gurugram, Haryana (DTCP Haryana / GMDA)
Plot area	20 acres (80,937 sq m)
Abutting road width	24 m
Plot frontage	Not specified — derived from plot proportions
Sanctioned budget	₹300 Cr
Optimisation priority	Maximise returns (ROI-led)

2 · Recommended development concept

The **Yield Max** concept — Density-led concept that maximises saleable area and revenue

DEVELOPMENT METRIC	VALUE
Floor Area Ratio (FAR) utilised	3.00
Ground coverage	44%
Maximum floors	10
Built-up area	2,42,812 sq m (26,13,604 sq ft)
Saleable area	2,13,675 sq m (22,99,976 sq ft)
Total units	2,455
Green & open space	13%

Land-use allocation

LAND USE	SHARE	AREA
Residential	41%	33,184 sq m
Commercial	26%	21,044 sq m
Green & Open Space	13%	10,522 sq m
Roads & Circulation	13%	10,522 sq m
Social Amenities	4%	3,237 sq m
Utilities & Services	3%	2,428 sq m

Unit mix

UNIT TYPE	COUNT	AVG SIZE
2 BHK	906	95 sq m (1,023 sq ft)
3 BHK	343	135 sq m (1,453 sq ft)
Retail unit	1,033	55 sq m (592 sq ft)
Office unit	173	140 sq m (1,507 sq ft)

Concept highlights

- FAR 3.00 of 3.00 permissible — yield maximised
- 10-storey massing (~31 m), tallest of the three concepts
- Ground coverage 44% vs 40% cap — deliberate stretch, expect flags
- Commercial share stepped up for rental yield
- 2455 units at 88% saleable efficiency

3 • Regulatory compliance

Aggregate compliance score: **46/100** — 8 checks passed, 3 with warnings, 2 failed.

RULE & REFERENCE	REQUIRED	PROPOSED	STATUS
Maximum permissible FAR Density & Bulk · HBC 2017 §6.2 (FAR table)	≤ 3.00	3.00	✓ Pass
Maximum ground coverage Density & Bulk · HBC 2017 §6.3 (coverage table)	≤ 40%	44%	! Warning
Maximum building height Density & Bulk · HBC 2017 §6.4 · AAI (NOC) Rules 2015	No cap — AAI NOC required	31.0 m (10 floors)	✓ Pass
Minimum green & organised open space Open Space · HBC 2017 §7.1 · URDPFI Guidelines 2015	≥ 15%	13%	× Fail
Minimum front setback Setbacks · HBC 2017 §6.5(a) (scaled for 31.0 m height)	≥ 9.0 m	9.9 m	✓ Pass
Minimum side setback Setbacks · HBC 2017 §6.5(b) (scaled for 31.0 m height)	≥ 6.0 m	5.7 m	! Warning
Minimum rear setback Setbacks · HBC 2017 §6.5(c) (scaled for 31.0 m height)	≥ 6.0 m	6.6 m	✓ Pass
Equivalent Car Spaces (ECS) Parking · HBC 2017 §8.2 · NBC 2016 Part 4 (parking norms)	≥ 3,643 ECS (@ 1.5 / 100 sq m)	2,478 ECS (2 basement/podium levels + surface)	× Fail
Abutting road width for high-rise Fire & Life Safety · NBC 2016 Part 4 §4.4 (fire appliance access)	≥ 12.0 m (height > 15 m)	24.0 m abutting road	✓ Pass
Refuge area provision Fire & Life Safety · NBC 2016 Part 4 §C-1.11 (refuge area)	Refuge floor every ≤ 15 m above 24 m	Refuge decks included in tower design	✓ Pass

RULE & REFERENCE	REQUIRED	PROPOSED	STATUS
Rainwater harvesting Environment · CGWA Notification 2020 · MoHUA model bylaws	Mandatory (plot > 100 sq m)	Recharge pits provided (~1 per 500 sq m of plot)	✓ Pass
Prior Environmental Clearance (EC) Environment · EIA Notification 2006, Schedule 8(a)	EC if built-up $\geq$ 20,000 sq m	2,42,812 sq m built-up	! Warning
EWS / affordable housing quota Inclusive Housing · HBC 2017 §9.1 · state affordable housing policy	N/A — applies to group housing / township	Not applicable	✓ Pass

Actions required

- **Maximum ground coverage:** Reduce footprint to $\leq$ 40% of plot by stacking floors or shrinking the podium.
- **Minimum green & organised open space:** Convert ~1,619 sq m of paved/roads area to landscaped open space to reach 15%.
- **Minimum side setback:** Pull the side building line back by 0.3 m — trim the podium edge or slim the tower floor plate.
- **Equivalent Car Spaces (ECS):** Short by 1,165 ECS — add a third basement level or mechanical stack parking.
- **Prior Environmental Clearance (EC):** Obtain EC from SEIAA before construction.

4 • Financial feasibility

Development cost

COST HEAD	AMOUNT
Land development & site works	₹60 Cr
Construction	₹813 Cr
Infrastructure & services	₹89.4 Cr
Approvals, fees & consultants	₹81.3 Cr
Marketing & sales	₹129 Cr
Finance cost	₹102 Cr
Contingency	₹48.1 Cr
Total development cost	₹1,323 Cr

Revenue

REVENUE STREAM	AMOUNT
Residential sales — 14,07,448 sq ft	₹1,900 Cr
Commercial sales / lease value — 8,92,528 sq ft	₹1,785 Cr
Total revenue	₹3,685 Cr

Key outcomes

Gross development profit	₹2,363 Cr
Project ROI	178.6%
Indicative payback period	4.9 years
Viability assessment	54/100 — Viable with caveats
Budget fit	Total cost is 441% of the ₹300 Cr budget (100% = exactly on budget)

Sensitivity analysis

WHAT-IF SCENARIO	RESULTING ROI
Base case	178.6%
Construction cost +10%	156.8%
Sale price –10%	153.2%
Sale price +10%	203.5%
6-month delay	175.9%

Assumptions

- Land assumed already owned — acquisition cost excluded; ROI is the development margin on owned land
- Construction cost ₹3,110/sq ft of built-up (blended residential/commercial by land-use split)
- Sale price: residential ₹13,500/sq ft, commercial ₹20,000/sq ft of saleable area
- Land development & site works ₹3 Cr per acre
- Infrastructure & services at 11% of construction cost
- Approvals, fees & consultants at 10% of construction cost
- Marketing & sales at 3.5% of gross revenue
- Finance at 9% p.a. on 60% of hard costs for half the 3 yr 11 mo build period
- Contingency at 5% of hard costs
- Price growth of 7.5% p.a. not compounded into base revenue (conservative)

5 • Construction roadmap

Estimated programme duration: **3 yr 11 mo** across 5 phases.

PHASE	START	DURATION	PEAK CREW
Approvals & Mobilization RERA registration & escrow account setup (RERA Act 2016) · Building plan sanction (DTCP Haryana) · Environmental clearance & NOCs (fire, AAI, pollution) · Site office, stores & labour camp mobilization · Contractor finalisation & mobilization advance	Month 1	8 mo	64
Site Development & Infrastructure Site clearing, grading & survey benchmarks · Internal roads & utility-corridor earthwork · Storm-water drainage & sewer network · Water lines, substation & DG-yards enabling works	Month 6	1 yr 1 mo	372
Structure Excavation & raft foundation · RCC frame — cores, columns & slab cycles (IS 456:2000) · Blockwork & masonry trailing the frame · Stair & lift cores, OH tanks & waterproofing	Month 9	2 yr	1,063

PHASE	START	DURATION	PEAK CREW
MEP & Finishes MEP first fix — electrical, plumbing risers, fire mains (NBC 2016 Part 4) · Façade, glazing & external plaster · Flooring, doors-windows & internal finishes · Lifts, DG sets, STP & fire systems — testing & commissioning	Month 20	2 yr 1 mo	850
External Development & Handover Landscaping, external lighting & signage · Occupancy certificate (OC) application & authority inspections · Snagging, deep cleaning & unit handover	Month 41	7 mo	266

Key milestones

- **Month 4** — RERA registration obtained
- **Month 8** — Building plans sanctioned
- **Month 9** — Groundbreaking — excavation begins
- **Month 13** — Plinth level completed
- **Month 32** — Structure topped out
- **Month 44** — Occupancy certificate received
- **Month 45** — Unit handover begins

Workforce plan

ROLE	COUNT
Project manager	4
Site engineers	37
Supervisors / foremen	58
Skilled workers (bar benders, masons, carpenters)	468
MEP technicians	128
Unskilled labour	319
Safety officers	5
Store & QA/QC staff	21

Major materials

MATERIAL	ESTIMATED QUANTITY
Cement (OPC/PPC, 50 kg bags)	10.5 lakh bags
TMT steel (Fe 500D)	9,148 MT
Ready-mix concrete	1.18 lakh m³
Fly-ash bricks (modular)	2.09 crore nos
Sand (river / M-sand)	1.33 lakh m³
Coarse aggregate (20 mm)	99,853 m³

Disclaimer. This report contains demo-grade, AI-generated estimates produced by the UrbanOS MVP for illustration only. Figures, bylaw interpretations, and timelines are indicative and do not constitute architectural,

engineering, legal, or investment advice. Verify all parameters with licensed professionals and confirm applicable regulations with the relevant sanctioning authority (DTCP Haryana / GMDA) before making any decision.