

Mannu house

AI-generated development appraisal — Balanced Urban concept

Generated on 19 July 2026 · Gurugram, Haryana · Sanctioning authority: DTCP Haryana / GMDA

1 · Project brief

Project name	Mannu house
Development type	Independent House
Jurisdiction	Gurugram, Haryana (DTCP Haryana / GMDA)
Plot area	1 acres (4,047 sq m)
Abutting road width	18 m
Plot frontage	80 m
Sanctioned budget	₹100 Cr
Optimisation priority	Sustainability-led
Client notes	10 bedroom rooms villa with high ceiling, with 10 parking space and patio and add pool to it 6 ft deep in square 30x30 ft.

2 · Recommended development concept

The **Balanced Urban** concept — Fully compliant, market-standard development

DEVELOPMENT METRIC	VALUE
Floor Area Ratio (FAR) utilised	1.75
Ground coverage	53%
Maximum floors	4
Built-up area	7,082 sq m (76,230 sq ft)
Saleable area	6,020 sq m (64,799 sq ft)
Total units	1

DEVELOPMENT METRIC	VALUE
Green & open space	42%

Land-use allocation

LAND USE	SHARE	AREA
Residential	53%	2,145 sq m
Green & Open Space	42%	1,700 sq m
Roads & Circulation	4%	162 sq m
Utilities & Services	1%	40 sq m

Unit mix

UNIT TYPE	COUNT	AVG SIZE
Dwelling floors (G+3)	4	1,771 sq m (19,063 sq ft)
Bedrooms	6	16 sq m (172 sq ft)
Covered car spaces	4	28 sq m (301 sq ft)

Concept highlights

- FAR 1.75 (~88% of cap) keeps approval headroom
- Compliant on coverage, height, setbacks and green norms
- 42% landscaped open space with pocket parks
- Family home of 7082 sqm with garden on three sides

3 • Regulatory compliance

Aggregate compliance score: **100/100** — 13 checks passed, 0 with warnings, 0 failed.

RULE & REFERENCE	REQUIRED	PROPOSED	STATUS
Maximum permissible FAR Density & Bulk · HBC 2017 §6.2 (FAR table)	≤ 2.00	1.75	✓ Pass
Maximum ground coverage Density & Bulk · HBC 2017 §6.3 (coverage table)	≤ 60%	52.6%	✓ Pass
Maximum building height Density & Bulk · HBC 2017 §6.4 · AAI (NOC) Rules 2015	No cap — AAI NOC required	12.4 m (4 floors)	✓ Pass
Minimum green & organised open space Open Space · HBC 2017 §7.1 · URDPFI Guidelines 2015	≥ 15%	42%	✓ Pass
Minimum front setback Setbacks · HBC 2017 §6.5(a) (scaled for 12.4 m height)	≥ 6.0 m	6.6 m	✓ Pass
Minimum side setback Setbacks · HBC 2017 §6.5(b) (scaled for 12.4 m height)	≥ 3.0 m	3.3 m	✓ Pass
Minimum rear setback Setbacks · HBC 2017 §6.5(c) (scaled for 12.4 m height)	≥ 3.0 m	3.3 m	✓ Pass
Equivalent Car Spaces (ECS) Parking · HBC 2017 §8.2 · NBC 2016 Part 4 (parking norms)	≥ 107 ECS (@ 1.5 / 100 sq m)	134 ECS (2 basement/podium levels + surface)	✓ Pass
Abutting road width for high-rise Fire & Life Safety · NBC 2016 Part 4 §4.4 (fire appliance access)	N/A — not a high-rise (≤ 15 m)	18.0 m abutting road	✓ Pass
Refuge area provision Fire & Life Safety · NBC 2016 Part 4 §C-1.11 (refuge area)	N/A — height ≤ 24 m	12.4 m tower height	✓ Pass
Rainwater harvesting	Mandatory (plot > 100 sq m)	Recharge pits provided (~1 per 500 sq m of plot)	✓ Pass

RULE & REFERENCE	REQUIRED	PROPOSED	STATUS
Environment · CGWA Notification 2020 · MoHUA model bylaws			
Prior Environmental Clearance (EC) Environment · EIA Notification 2006, Schedule 8(a)	EC if built-up ≥ 20,000 sq m	7,082 sq m built-up	✓ Pass
EWS / affordable housing quota Inclusive Housing · HBC 2017 §9.1 · state affordable housing policy	N/A — applies to group housing / township	Not applicable	✓ Pass

Actions required

No remediation actions — all checks passed for this concept.

4 • Financial feasibility

Development cost

COST HEAD	AMOUNT
Land acquisition	₹55 Cr
Land development & site works	₹3 Cr
Construction	₹16.8 Cr
Infrastructure & services	₹1.34 Cr
Approvals, fees & consultants	₹1.68 Cr
Marketing & sales	₹0 Cr
Finance cost	₹0.71 Cr
Contingency	₹1.06 Cr
Total development cost	₹79.6 Cr

Revenue

REVENUE STREAM	AMOUNT
Estimated completed value	₹68 Cr
Total revenue	₹68 Cr

Key outcomes

Gross development profit	₹-11.5 Cr
Project ROI	-14.5%
Indicative payback period	Not recovered at projected prices
Viability assessment	56/100 — Viable
Budget fit	Total cost is 80% of the ₹100 Cr budget (100% = exactly on budget)

Sensitivity analysis

WHAT-IF SCENARIO	RESULTING ROI
Base case	-14.5%
Construction cost +10%	-16.7%
Sale price –10%	-23%
Sale price +10%	-5.9%
6-month delay	-14.8%

Assumptions

- Land acquisition at ₹55 Cr per acre (city-average demo benchmark; equity-funded, excluded from the finance-cost base)
- Construction cost ₹2,200/sq ft of built-up
- Sale price: residential ₹10,500/sq ft, commercial ₹20,000/sq ft of saleable area
- Land development & site works ₹3 Cr per acre
- Infrastructure & services at 8% of construction cost
- Approvals, fees & consultants at 10% of construction cost
- Marketing & sales at 3.5% of gross revenue (waived for self-use house)
- Finance at 9% p.a. on 60% of hard costs for half the 1 yr 3 mo build period
- Contingency at 5% of hard costs
- Price growth of 7.5% p.a. not compounded into base revenue (conservative)

5 · Construction roadmap

Estimated programme duration: **1 yr 3 mo** across 5 phases.

PHASE	START	DURATION	PEAK CREW
Approvals & Mobilization Building plan sanction (DTCP Haryana) · Soil investigation & structural design · Site office, stores & labour camp mobilization · Contractor finalisation & mobilization advance	Month 1	3 mo	3
Site Development & Infrastructure Site clearing, grading & survey benchmarks · Boundary wall & plot drainage · Temporary power & water connections	Month 3	4 mo	11
Structure Excavation & isolated & strip footings · RCC frame — plinth to roof slab (IS 456:2000) · Blockwork & masonry trailing the frame · Stair & lift cores, OH tanks & waterproofing	Month 4	8 mo	30

PHASE	START	DURATION	PEAK CREW
MEP & Finishes Electrical conduiting & plumbing first fix · Internal plaster, flooring & tiling · Doors, windows, painting & fixtures	Month 8	7 mo	24
External Development & Handover Landscaping, external lighting & signage · Completion certificate application (DTCP Haryana) · Snagging, deep cleaning & unit handover	Month 14	2 mo	8

Key milestones

- **Month 3** — Building plans sanctioned
- **Month 4** — Groundbreaking — excavation begins
- **Month 5** — Plinth level completed
- **Month 11** — Structure topped out
- **Month 14** — Completion certificate received
- **Month 15** — Handover & possession

Workforce plan

ROLE	COUNT
Project manager	1
Site engineers	1
Supervisors / foremen	2
Skilled workers (bar benders, masons, carpenters)	13
MEP technicians	4
Unskilled labour	9
Safety officers	1
Store & QA/QC staff	1

Major materials

MATERIAL	ESTIMATED QUANTITY
Cement (OPC/PPC, 50 kg bags)	30,492 bags
TMT steel (Fe 500D)	267 MT
Ready-mix concrete	3,430 m³
Fly-ash bricks (modular)	6.1 lakh nos
Sand (river / M-sand)	3,883 m³
Coarse aggregate (20 mm)	2,912 m³

Disclaimer. This report contains demo-grade, AI-generated estimates produced by the UrbanOS MVP for illustration only. Figures, bylaw interpretations, and timelines are indicative and do not constitute architectural, engineering, legal, or investment advice. Verify all parameters with licensed professionals and confirm applicable regulations with the relevant sanctioning authority (DTCP Haryana / GMDA) before making any decision.